

# VERNON COUNTY CERTIFIED U.S. PUBLIC LAND SURVEY MONUMENT RECORD

INSTRUCTIONS: THIS RECORD SHALL SHOW THE LOCATION OF THE CORNER AND SHALL INCLUDE ALL OF THE FOLLOWING ELEMENTS (A-I)

(A) IDENTIFY THE CORNER BY REFERENCE TO THE U.S. PUBLIC LAND SURVEY SYSTEM

■ = CORNER MONUMENT RESTORED

WITNESSES TO CORNER LOCATION:

- 1) Robert M. Lampman
- 2) Jessica A. Zamor

VERNON COUNTY COORDINATES - NAD83(1991) - SURVEY FEET


NORTHING: 210977.380

EASTING: 785781.162

MONROE COUNTY COORDINATES - NAD83(1991) - SURVEY FEET

NORTHING: 300035.778

EASTING: 689329.892



SECTION 1  
TOWN 14 NORTH, RANGE 2 WEST

(B) DESCRIBE ANY RECORD EVIDENCE, MONUMENT EVIDENCE, OCCUPATIONAL EVIDENCE, TESTIMONIAL EVIDENCE OR ANY OTHER MATERIAL EVIDENCE YOU CONSIDERED, AND WHETHER THE MONUMENT WAS FOUND OR PLACED.

Accepted location of existing Army Corps of Engineers Monument (brass capped iron pipe) at the occupied fence corner as the best available evidence of the original corner location.

(See corner history on reverse side of sheet.)

(C) IN THE PLAN VIEW DRAWING BELOW, PROVIDE REFERENCE TIES TO AT LEAST 4 WITNESS MONUMENTS OR, IF THE LOCATION IS WITHIN A MUNICIPALITY, TO AT LEAST 2 WITNESS MONUMENTS. (WITNESS MONUMENTS SHALL BE MADE OF CONCRETE, NATURAL STONE, IRON, OR OTHER EQUALLY DURABLE MATERIAL.) DESCRIBE WITNESS MONUMENTS.

(D) SHOW A PLAN VIEW DRAWING, DEPICTING THE RELEVANT MONUMENTS AND REFERENCE TIES, WHICH IS SUFFICIENTLY DETAILED TO ENABLE ACCURATE RELOCATION OF THE CORNER MONUMENT IF IT IS DISTURBED.

NOT TO SCALE



N 33°16'47" W 35.73'  
Set 3/4" Iron Bar  
4'± South of 12" Ash

WOODED PASTURE

Set 2" Channel Post  
with Sign 1.3' ± East  
of Corner

WOODED PASTURE

N 44°43'26" E 14.12'  
Set 3/4" Iron Bar  
9.4'± North of Fence  
& 10.7'± East of Fence

S 67°11'42" E 17.61'  
Set 3/4" Iron Bar  
1.2'± West of  
Double Elm

WOODED

S 08°54'12" E 23.96'  
Set 3/4" Iron Bar  
2.8'± North of  
5" Maple

123

### LEGEND

- FOUND EXISTING IRON PIPE WITH BRASS CAP (U.S.A.C.E.)
- SET 3/4" X 24" ROUND IRON BAR FOR WITNESS MONUMENT

WOODED PASTURE

(E) DESCRIBE ANY MATERIAL DISCREPANCY BETWEEN THE LOCATION OF THE CORNER AS RESTORED OR REESTABLISHED AND THE LOCATION OF THAT CORNER AS PREVIOUSLY RESTORED OR REESTABLISHED BY DISTANCE AND DIRECTION. SHOW THE DISCREPANCY ON THE PLAN VIEW DRAWING UNDER (D), ABOVE. SHOW THE DISTANCES BETWEEN THE CORNER AS PREVIOUSLY RESTORED OR REESTABLISHED AND (1) THE CORNER AS RESTORED OR REESTABLISHED, AND (2) TO AT LEAST 2 OF THE WITNESS MONUMENTS AS SHOWN ON THE DRAWING IN (D), ABOVE.

N/A

(F) WAS THE CORNER RESTORED THROUGH ACCEPTANCE OF (1) AN OBLITERATED EVIDENCE LOCATION, OR (2) A FOUND PERPETUATED LOCATION?

(2) A FOUND PERPETUATED LOCATION

(G & H) WAS THE CORNER REESTABLISHED THROUGH LOST CORNER PROPORTIONATE METHODS? IF SO SHOW THE METHOD, INCLUDING THE DIRECTIONS AND DISTANCES TO OTHER PUBLIC LAND SURVEY CORNERS USED AS EVIDENCE OR USED FOR PROPORTIONING IN DETERMINING THE CORNER LOCATION.

N/A

(\*\*) ANY ADDITIONAL INFORMATION RELATED TO CORNER LOCATION

**CORNER HISTORY:**

-Original government corner location established by Uriah Biggs in 1845.

-Alex Ristow utilized the corner during a subdivision of Section 1, T14N, R2W dated January of 1906. Ristow's survey lists the corner as government, does not include notation of any particular type of monument at the corner and does not include any witnesses.

-Ralph J. Van Dorpe, Illinois Registered Land Surveyor for the U.S. Army Corps of Engineers reestablished this corner as part of a property survey for the Kickapoo River Reservoir during 1965 and 1966. Plat of Survey prepared by Van Dorpe calls for a 1" iron pipe with brass cap at this corner. Van Dorpe reestablished the corner location by acceptance of occupation at the corner.

-William C. Jung recovered the Army Corps monument and prepared a tie sheet dated January of 1981.

-Patrick Carroll shows a 1" iron pipe at the corner on survey dated May of 2000 and located in part of Section 1, T14N, R2W.


-Patrick Carroll shows a 1" iron pipe (Corp. of Eng. Cap) found in place on a survey dated October of 2002 and located in part of Section 1, T14N, R2W.

AFFIX LAND SURVEYOR SEAL

(I) I, ROBERT M. LAMPMAN, CERTIFY THAT THE LOCATION SHOWN ON THIS RECORD WAS DETERMINED BY ME OR UNDER MY DIRECTION AND CONTROL AND THAT THIS U.S. PUBLIC LAND SURVEY MONUMENT RECORD IS CORRECT AND COMPLETE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

  
SIGNATURE

3-10-04  
DATE



I, William C. Jung, do hereby certify that on the 26th day of March 19 80, I found (evidence) ~~(no evidence)~~ of the SE corner of Section 35, T 15 N, R 2 W Fourth Principal Meridian, and I re-established said corner according to the Wisconsin Statutes as shown and described hereon.

History of corner establishment since Original Government Survey

The U.S. Army Corps of Engineers set a 1 1/2" capped pipe at the occupied corner in 1965.

Description of corner evidence found:

I found the U.S.A.C.E. pipe and accepted it as the corner.

Dated this 19th day of Jan. 19 81.

William C. Jung




William C. Jung, R.L.S. 1323

COUNTY SURVEYOR FORM NO. 1

Description of corner and witness monuments, references and accessories used to perpetuate the original or re-established location of this corner:

Witnesses to corner location:

- W. Jung
- C. Pietz
- M. Scott Sowers



Approved: HARLEY A. SIME  
MONROE CO. SURVEYOR

SURVEY CONTROL ORDER

Horizontal	_____
Vertical	_____

WISCONSIN COORDINATE SYSTEM

Corner	East (X)	North (Y)	Elevation (Z)	Zone
Control Sta. Name				

(All trees are double blazed with N&C's set)

~~City, Village~~ or Town Sheldon  
County of Monroe