


DESCRIPTION: Those lands as intended to be described and conveyed in Vol. 133 D., Page 431 at document number 161281 as recorded in the Monroe County Register of Deeds Office in Sparta, Wisconsin, said lands are more particularly described as follows: All that part of the SE $\frac{1}{4}$ -SW $\frac{1}{4}$, Section 11, T15N, R1W, Town of Wellington, Monroe County, Wisconsin, lying Northerly, Westerly and Southerly of the following described line: Commencing at the South $\frac{1}{4}$ corner of said Section 11; thence S89°57'46"W, along the South line of the said SE $\frac{1}{4}$ -SW $\frac{1}{4}$, 1216.28 feet; thence N0°02'14"W, 340.99 feet, to a point on the projection of the North line of Lot 2 of Vol. 7 CSM, Page 63 (projected Northeasterly), being a point in the centerline of a town road (hereinafter referred to as Point "A") and the point of beginning; thence Northeasterly along the arc of a curve concave to the Southeast, having a radius of 385.56 feet (the long chord of which bears N52°56'11"E, 216.14 feet), 219.07 feet, along said centerline; thence N69°12'50"E, along said centerline, 150.00 feet; thence N66°08'38"E, along said centerline, 41.75 feet; thence N9°53'08"W, 249.66 feet; thence S86°31'41"W, 160.68 feet; thence N81°05'49"W, 137.35 feet; thence N66°24'08"W, to the West line of the said SE $\frac{1}{4}$ -SW $\frac{1}{4}$ and the end of said line; also those lands lying Northerly of the following described line: Beginning at afore mentioned point "A"; thence S82°28'04"W, along the projection of the North line of said Lot 2 and the North line of said Lot 2, to the West line of the said SE $\frac{1}{4}$ -SW $\frac{1}{4}$ and the end of said line. the lands described above are subject to any and all easements, covenants, restrictions and rights-of-way of record.

CLIENT WAIVER: I, as client, hereby waive A-E 7.05 (3) and A-E 7.04 of the Wisconsin Administrative Code in that the exterior boundary dimensions are not all shown and that the west line of the SE $\frac{1}{4}$ -SW $\frac{1}{4}$ of Section 11 was not actually located or determined due to cost factors.

Ronald J. Olson 10/27/95
 Client Date

SURVEYOR'S CERTIFICATE: I, Bryan H. Meyer, being a duly qualified surveyor, do hereby certify that by the order and under the direction of Corrine Schendel, I have surveyed and mapped the lines described above and that the within map is a true and correct representation of the lines surveyed, to the best of my knowledge and belief.


Bryan H. Meyer
 Bryan H. Meyer, Registered Land Surveyor
 H. A. Sime and Associates
 P. O. Box 705, Tomah, Wisconsin
 Phone: (608)-372-5392



Vol. 133 D,
 Page 431

A-B
 CURVE DATA
 $\Delta = 32^\circ 33' 18''$ R = 385.56'
 LC = N52°56'11"E, 216.14'
 A = 219.07'

SURVEYOR'S NOTE: The lines surveyed and shown hereon are what in my opinion are the Northerly, Easterly and Southerly lines of lands as intended to be described and conveyed in Vol. 133 D., Page 431. The Northerly and Easterly lines have well established fencelines along them. Consult your attorney relative to assuring or clearing up the title to the lands involved.




Dated this 15th day of September, 1995,
 at Tomah, Wisconsin.

The bearings shown on this map are referenced to the South line of the SW $\frac{1}{4}$ of Section 11; said line is ASSUMED to bear N89°57'46"E.



SCALE: 1" = 100'

- ⊙ = Existing cast iron marker
- = Existing 3/4" round iron bar
- = Set 3/4" x 24" round iron bar weighing 1.50 lbs./lin. ft.



PLAT OF SURVEY

Located in the SE $\frac{1}{4}$ -SW $\frac{1}{4}$, Section 11, T15N, R1W, Town of Wellington, Monroe County, Wisconsin.



Reference file number 3388